this account this contract has to be cancelled and other arrangements made for the excution or completion of the work. He will also be held liable for any loss or extra amount of expenditure that may have to be incurred or paid and such amount would be recovered from him either as arrears of land revenue or in any manner considered suitable.

8. No interest will be allowed on the security amount deposited with the Chief Auditor, Mysore State Railway, nor on any money retained by the Administration.

9. The accepted rate will hold vaild till the entire work is completed and claims for enhanced rates will not be entertained under any circumstances for tendered items of work.

**Schedule.**

Approximate quantities of works to be done for improvements to Labourers' Quarters near Railway Central Workshops and drainage arrangements at Mysore South.

| Sl. No. | Items of work | Unit | Quantity | Rate in figures | Rate in words |
|---|---|---|---|---|---|
| | IMPROVEMENTS TO QUARTERS. | | | | |
| 1 | Excavation in all soils including excavated earth and tamping ... ... ... | 1000 C.ft. | 2,587 | ... | ... |
| 2 | Filling in excavated earth including tamping ... ... ... ... | ,, | 888 | ... | ... |
| 3 | Concrete of broken granite jelly in railway cement 1 : 3 : 6 ... ... ... | 100 C.ft. | 216 | ... | ... |
| 4 | Masonry contractor's burnt brick in lime founds and plinth ... ... ... | ,, | 2,317 | ... | ... |
| 5 | Do in prepared mud ... ... ... ... | ,, | 3,566 | ... | ... |
| 6 | Dressed stone lintels 4" to 6" thick including fixing ... ... ... ... | C.ft. | 172 | ... | ... |
| 7 | T. W. doors with battened shutters including all fittings complete as per marryat's specifications | S.ft. | 954 | ... | ... |
| 8 | T. W. windows with battened shutters ⅜" dia. M. S. bars and all fittings complete as per marryat's specifications | ,, | 544½ | ... | ... |
| 9 | Fixing doors including frames ... ... ... ... ... | Each | 54 | ... | ... |
| 10 | Fixing windows do ... ... ... ... ... | ,, | 66 | ... | ... |
| 11 | Lifting and fixing rails in buildings ... ... ... ... | Ton | 14·59 | ... | ... |
| 12 | Fixing deptl. asbestos sheets on roofing with depth bolts. and nuts ... ... ... | 100 S.ft. | 5,184 | ... | ... |
| 13 | T. W. wrought and put up including wood oiling two coats ... ... ... | C.ft. | 268·16 | ... | ... |
| 14 | Roofing with contractor's first class Mangalore tiles on teak reepers 2"×1" including chunam borders 9" wide ×4½" thick teakwood wind tiles 2"×2" etc., complete. | 100 S.ft. | 7,708 | ... | ... |
| 15 | Setting contractor's ridge tiles in lime mortar ... ... ... ... ... | 100 R.ft. | 800 | ... | ... |
| 16 | Supplying and fixing ventilating tiles ... ... ... ... ... | Each | 24 | ... | ... |
| 17 | Do glass tiles Mangalore pattern ... ... ... ... | ,, | 24 | ... | ... |
| 18 | Fixing gutters with Deptl. G. I. sheets ... ... ... ... | S.ft. | 2,486 | ... | ... |
| 19 | Plastering in lime brick masonry ... .. ... ... ... | 100 S.ft. | 13,958 | ... | ... |
| 20 | White washing two coats ... ... ... ... ... | ,, | 13,958 | ... | ... |
| 21 | Flooring with 1½" thick cement concrete on 3" lime concrete including plastering ½" thick (cement supplied departmentally). | ,, | 7,987 | ... | ... |
| 22 | Painting two coats with contractor's chocolate paint ... ... ... ... | ,, | 4,810 | ... | ... |
| 23 | Providing sinks 2'×2' ... ... ... ... ... ... | Each | 66 | ... | ... |
| 24 | Providing ovens ... ... ... ... ... ... | ,, | 66 | ... | ... |
| 25 | Supplying and fixing G. I. down water pipes 4" dia. with contractor's materials ... ... | R.ft. | 742 | ... | ... |
| 26 | Providing masonry drain 6" with brick in lime at sides, lime concrete 4" thick at bottom including plastering in depti cement and covering with 4" thick one line dressed granite slabs complete. | ,, | 1,150 | ... | ... |
| 27 | Plastering in Railway cement ... ... ... ... ... | 100 S.ft. | 504 | ... | ... |
| 28 | Providing washing place, one line dressed slabs 4" thick fixed on the top of burnt brick in lime masonry 2½' high by 1½' wide including plastering in Railway cement with necessary slope. | Each | 66 | ... | ... |
| 29 | Lime mortar bunds 9"×4½" on roofs including plastering .. ... ... | 100 R.ft. | 909 | .. | |
| 30 | Dismantling masonry (brick in mud) ... ... ... ... ... | 100 C.ft. | 1,450 | ... | ... |
| 31 | Do do (in lime) ... ... ... ... ... | ,, | 192 | ... | ... |
| 32 | Removing and refixing windows including frames ... ... ... ... | Each | 18 | ... | ... |
| 33 | Do do doors do ... ... ... ... | | 51 | ... | ... |
| 34 | Shifting existing mortar and pestle in building to the new places including fixing ... ... | ,, | 12 | ... | ... |
| | II. PROVIDING DRAINAGE ARRANGEMENTS AND CISTERNS. | | | | |
| 1 | Excavation in all soils and spreading the excavated earth including levelling ... ... | 1000 C.ft. | 3,226 | ... | ... |
| 2 | Concrete of granite broken jelly in railway cement 1 : 3 : 6 ... ... ... | 100 ,, | 1,372 | ... | ... |
| 3 | Dressed stone lintels 4" to 6" thick including fixing... ... ... ... | ,, | 4 | ... | ... |
| 4 | Masonry contractor's burnt brick in railway cement ... ... ... ... | 100 ,, | 2,890 | ... | ... |
| 5 | Do do in lime founds and plinth ... ... ... ... | ,, | 225 | ... | ... |
| 6 | Plastering in railway cement ... ... ... ... ... | 100 S.ft. | 17,655 | ... | ... |
| 7 | Supplying and fixing stoneware pipes 4" dia. in railway cement ... ... ... | R.ft. | 360 | ... | ... |
| 8 | Supplying and fixing C. I. frame with lid at top 2 ft. dia. on manhole ... ... | Set | 7 | ... | ... |
| 9 | Supplying and fixing gully traps ... ... ... ... ... | Each | 7 | ... | ... |
| 10 | Pipe trenching including filling in ... ... ... ... ... | 100 C.ft. | 2,880 | ... | ... |
| 11 | Flooring with 1½" cement concrete on 3" thick lime concrete including plastering in railway cement ½" thick. | 100 S.ft. | 3,400 | ... | ... |

N.B.—Contractor should make his own arrangements for water. All debris after completion of work should be removed at contractor's cost. Cement G. I. sheets, plain for gutters, asbestos sheets will be supplied departmentally free of cost to the contractors. Payment for doors and windows will be made on the clear dimensions between frames.

1025 S. RAJAGOPAL, Ag. *Dist. Engr.*

## OFFICE OF THE ASSISTANT DIRECTOR OF AGRICULTURE, KOLAR.

Auction Notification dated 3rd February 1949.

It is hereby notified for the information of the public that about 500 unserviceable gunny bags will be auctioned on 1st March 1949 between 11 A.M. and 2 P.M. at the premises of the Office of the Assistant Director of Agriculture, Kolar Circle, Kolar. Intending bidders have to deposit Rs. 25 in advance and be present there at the time The deposit excepting in the case of the successful bidder will be returned. The highest bidder will have to immediately deposit the amount and take the gunnies after approval is communicated.

8756 C. M. REVANNA, *Asst. Director.*

## TUMKUR DISTRICT.

(CIVIL SUPPLIES BRANCH).

Notification dated 1st—3rd February 1949.

**No. A. Y. 7—48-49.** Sealed tenders are invited from the intending contractors for the following items of work in Tumkur Town relating to the District Reserve godowns.

### I. Loading, Un-loading and Conveyance.

(a) Un-loading the bags from the wagons and (i) conveyance to the Depot located in the Railway Station yard and stacking (ii) conveyance to Nissen Shed godown just outside the Station Yard and stacking (iii) conveyance to any othe depot within Municipal limits and stacking (rate per bag to be mentioned).

(b) Un-loading of bags from Wagon, weighment at the platform scale and conveyance and stacking at (i) Railway Station Depot (ii) Nissen Shed go-downs (iii) any other go downs within Municipal limits (rate per bag to be mentioned)

(c) Loading and un-loading charges for grains conveyed by Government lorries including stacking (rate per bag).

### II. Weighing, bagging and stacking at the Depot.

(a) Weighment of grains at the Depots in the scale provided per bag and stacking.

(b) Measuring, rebagging stitching and stacking in rows—per bag (i) including materials for stitching (ii) excluding materials for stitching.

### III. Empty gunnies.

(a) Un-loading of empty gunnies from wagons and conveyance to (i) Railway Station Depot, (ii) Nissen Shed godown (iii) any other godown within Municipal Limits and stacking (per 100 bags).

(b) Loading of empty gunnies into wagons after conveying the same from (i) Railway Station Depot, (ii) Nissen Shed godown, (iii) Any other godown within Municipal Limit (per 100 bags).

(c) Loading and un-loading charges of 100 empty gunnies into Government lorries.

NOTE:—(i) Bag means a bag of 80 seers or 90 seers of foodgrains.
(ii) In respect of wheat products, bag of 196 lbs. (gross) will be taken as the standard.

(i) The tender should reach this office not later than 15*th February* 1949, 5 P.M.

(ii) Each tender should be accompanied by a treasury chellan for Rs. 100 for having credited as security deposit.

(iii) The tender is subject to the approval of the Director of Food Supplies in Mysore, Bangalore.

(iv) After approval, the successful tenderer will have to execute the necessary stamped agreement.

(v) The contractor will be required to supply labour as and when indented and get through the several items of work in time. He will be liable to pay any extra charges incurred by Government due to failure on his part to fulfil any of the conditions set forth in the agreement in addition to forfeiture of the security deposit.

8863 K. THIPPERUDRIAH, *Dy. Commr.*

## MADHUGIRI SUB-DIVISION.

Notification dated 27th January 1949.

**No. F. C. 12—48-49.** It is hereby notified for the information of the public that 2,000 unserviceable empty gunnies that are available in the Taluk Reserve Depot, Madhugiri, will be sold by the undersigned in a public sale on 26th February 1949 at the Taluk Reserve Depot premises, Madhugiri at 12 NOON. Intending bidders may come and offer their bids in the said public sale. Final bidder should abide the conditions of the sale. Further particulars may be had from the Amildar, Madhugiri Taluk.

8748 L. KRISHNA NAIK, *S.D.O.*

## OFFICE OF THE DIRECTOR, AKASHVANI BROADCASTING STATION, GOVERNMENT OF MYSORE, VANI VILAS MOHALLA, MYSORE.

Notification.

AUCTION SALE OF ONE FORD V—8 SEDAN CAR.

In is hereby notified for the information of the public that one Ford car of the following description will be sold in public auction at the premises of the Akashvani Broadcasting Station, Vani Vilas Mohalla, Mysore, on Thursday the 17th February 1949 between 9 A.M. and 11 A.M. by the undersigned or an officer authorised by him.

The car will be available at the office and the intending bidders may inspect the car on any working day from 14th February 1949 between 4 P.M. and 6 P.M. The final bid will be subject to the approval of the Director, Akashvani, Mysore.

*Description* :—

Ford V-8 1936 Model touring Sedan car. 30 H. P. 5 seater in good running condition. The colour of the car is sky-blue and the vehicle is complete with fairly new tyres and tubes fitted to the four wheels and one spare stephney. The car bears the registered No. MYZ. 2034 and is covered by motor-insurance against third party risks up to 1st January 1950.

The terms of the sale are as follows :—

1. The car will be put up for detailed inspection one hour before the commencement of auction.
2. The vehicle will be sold to the highest bidder who should on the spot pay the bid amount in full and remove the vehicle immediately.
3. The decision of the undersigned is final in all matters regarding this sale.

8527 B. NARAYANASWAMY, *Director.*

## OFFICE OF THE HUZUR SECRETARY TO HIS HIGHNESS THE MAHARAJA OF MYSORE.

Tender Notice.

Sealed tenders for the supply of provisions, etc., to the Palace, for the year 1949-50, will be received by the undersigned on the 17th February 1949 at 3 P.M. Particulars can be had from the Muneeb, Palace Mothikhana, Mysore.

8193 H. NIRANJAN RAJ URS, *Huzur Secy.*

## OFFICE OF THE ASSISTANT DIRECTOR OF AGRICULTURE, MYSORE DISTRICT.

Abstract Notification.

The attention of the public is invited to this office notification dated 27th December 1948, published in *Mysore Gazette*, Page 87, Part VI dated 27th January 1949, calling for sealed tenders in connection with the transport of seeds manures and miscellaneous articles in Mysore District.

8421 N. RAMANNA, *Asst. Director.*

## GOVERNMENT SANDALWOOD OIL FACTORY, MYSORE.

Notification dated 20th January 1949.

Sealed tenders will be received by the General Manager, Government Sandalwood Oil Factory, Mysore, up to 3 P.M. of 15th February 1949, for the purchase of a used Chevrolet Lorry of the following description, belonging to the Factory.

Each tender must be accompanied by a deposit of Rs. 500 in cash as earnest money and should be inscribed "Tender for purchase of Chevrolet Lorry."

Final acceptance of the tender will rest with the Director of Sandalwood Factories in Mysore, Bangalore, who does not bind himself to accept or reject any tender or to assign any reasons therefor. The tenders will be opened at 4 P.M. on 15th February 1949 by the undersigned in the presence of such of the tenderers as are present at the time.

The successful tenderer should pay the balance amount of the price offered by him for the lorry within TEN DAYS from the date of acceptance of the tender and take delivery of the vehicle.

Should the tenderer, whose tender is accepted, fail to pay the balance amount of the tender and take delivery of the lorry within the time mentioned above, the amount deposited will be forfeited and the lorry exposed for resale at his risk.

The Lorry put up for sale may be inspected at the premises of the Factory on any working day between 8 A.M. and 12 NOON and 1 P.M. and 5 P.M.

**Description of the Vehicle.**

| | | | |
|---|---|---|---|
| 1 | Name of the Vehicle | ... | Chevrolet No. XXTC. 3641 and Engine TR 1491-279 : 3235 Fitted with semi-saloon body. |
| 2 | Size of the body | ... | L. B. H. $11\frac{1}{4}'' \times 5''-7'' \times 4\frac{1}{2}''$ |
| 3 | Registration No. | ... | MYZ 4230. |
| 4 | Model | ... | 1938. |
| 5 | When purchased | ... | January 1939. |
| 6 | Weight of chassis | ... | Tons. 2–7–2 drs. (Tare) |
| 7 | Lorry capacity | ... | Tons. 6–0–0 (Gross). |
| 8 | H. P. | ... | 29·4 H.P. |

Break certificate valid up to end of June 1949.

B. P. RAMAKRISHNA, *Genl. Manager.*

## OFFICE OF THE RANGE OFFICER, MINOR TANK RESTORATION RANGE, FRENCH-ROCKS.

Tender Notification dated 28th January 1949.

Sealed tenders will be received by the undersigned till 4 P.M. on Monday the 21st February 1949, for the work of increasing the capacity of Malagoor Tank in Krishnarajapet Taluk.

1. The work is estimated to cost Rs. 27,500.
2. Each tender should accompany a treasury chellan for having credited Rs. 1,375 to any of the Government Treasuries towards the earnest money under "40 (1) Remittances to P.W.D." in favour of the Range Officer, Minor Tank Restoration Range, French-rocks.
3. Tenderers should quote their rates against each item of work and not percentage more and less either on individual rates or on the estimated cost.
4. Covers should be superscribed as "Tender for increasing the capacity of Malagoor Tank", with the name of the tenderer.
5. All tenders should hold good until it is finally disposed of by the accepting authority.
6. For all lumpsum items and non-tendered items only the minimum rates of the current year's sanctioned schedule of rates of this Range will be given.